



INVESTOR IN PEOPLE

CERTIFIED COPY OF PRIORITY DOCUMENT

The Patent Office
Concept House
Cardiff Road
Newport
South Wales
NP10 8QQ



I, the undersigned, being an officer duly authorised in accordance with Section 74(1) and (4) of the Deregulation & Contracting Out Act 1994, to sign and issue certificates on behalf of the Comptroller-General, hereby certify that annexed hereto is a true copy of the documents as originally filed in connection with the patent application identified therein.

In accordance with the Patents (Companies Re-registration) Rules 1982, if a company named in this certificate and any accompanying documents has re-registered under the Companies Act 1980 with the same name as that with which it was registered immediately before re-registration save for the substitution as, or inclusion as, the last part of the name of the words "public limited company" or their equivalents in Welsh, references to the name of the company in this certificate and any accompanying documents shall be treated as references to the name with which it is so re-registered.

In accordance with the rules, the words "public limited company" may be replaced by p.l.c., plc, P.L.C. or PLC.

Re-registration under the Companies Act does not constitute a new legal entity but merely subjects the company to certain additional company law rules.

Signed

Dated 8th March 2001

This Page Blank (uspto)

10 JAN 2001

**The
Patent
Office**


1/77

11JAN01 E597058-1 D00611
P01/7700 0.00-0100668.3

Patents Act 1977

Rule 16

Request for grant of a patent



The Patent Office

Concept House:
Cardiff Road
Newport
South Wales NP10 8QQ

1. Your reference GB920000108GB1

2. Patent application number
(The Patent Office will fill in this part) **0100668.3**

3. Full name, address and postcode of the or of each applicant (*underline all surnames*) INTERNATIONAL BUSINESS MACHINES CORPORATION
Armonk
New York 10504
United States of America

Patents ADP number (*if you know it*)

519637001

If the applicant is a corporate body, give the country/state of its incorporation

State of New York
United States of America

4. Title of the invention PROVISION OF POSITION INFORMATION IN CELLULAR NETWORK DATA TRANSMISSION

5. Name of your agent (*if you have one*) R D Moss

"Address for Service" in the United Kingdom to which all correspondence should be sent (*including the postcode*)

IBM United Kingdom Limited
Intellectual Property Department
Hursley Park
Winchester
Hampshire
SO21 2JN

Patents ADP number (*if you know it*)

919005.

6.	If you are declaring priority from one or more earlier patent applications, give the country and the date of filing of the or of each of these earlier applications and (<i>if you know it</i>) the or each application number	Country	Priority App No (<i>if you know it</i>)	Date of filing (<i>day/month/year</i>)

7.	If this application is divided or otherwise derived from an earlier UK application, give the number and the filing date of the earlier application	No of earlier application	Date of filing (<i>day/month/year</i>)

8

Is a statement of inventorship and of right to grant of a patent required in support of this request? (Answer 'Yes' if:

Yes

- a) any applicant named in part 3 is not an inventor, or
b) there is an inventor who is not named as an applicant, or
c) any named applicant is a corporate body.)

9.

Enter the number of sheets for any of the following items you are filing with this form. Do not count copies of the same document

Continuation sheets of this form

Description

8

Claim(s)

4

Abstract

1

Drawing(s)

2 *12*

8

10.

If you are also filing any of the following, state how many against each item.

Priority documents

Translations of priority documents

Statement of inventorship and right to grant of a patent (Patents Form 7/77)

2 *1*

Request for preliminary examination and search (Patents Form 9/77)

Request for substantive examination (Patents Form 10/77)

Any other documents (please specify)

11.

I/We request the grant of a patent on the basis of this application

R. D. Moss

Signature

9 January 2001
Date


12.

Name and daytime telephone number of person to contact in the United Kingdom

R D Moss
01962 818399

10 JAN 2001

**The
Patent
Office**



7/77

Patents Act 1977
Rule 15

**Statement of inventorship and of
right to grant of a patent**

The Patent Office

Concept House
Cardiff Road
Newport
South Wales NP10 8QQ

1. Your reference GB920000108GB1

2. Patent application number
(if you know it) **0100668.3**

3. Full name of the or of each applicant INTERNATIONAL BUSINESS MACHINES CORPORATION

4. Title of invention PROVISION OF POSITION INFORMATION IN CELLULAR
NETWORK DATA TRANSMISSION

5. State how the applicant(s) derived the right from the inventor(s) to be granted a patent By employment and agreement

6. How many, if any, additional Patents Forms 7/77 are attached to this form?

7. I/We believe that the person(s) named over the page (and on any extra copies of this form) is/are the inventor(s) of the invention which the above patent application relates to.

R. D. Moss

Signature

9 January 2001
Date

8. Name and daytime telephone number of person to contact in the United Kingdom R D Moss
01962 818399

Enter the full names, addresses and postcodes of the inventors in the boxes and underline the surnames

HARRIS, Robert
UK resident
c/o IBM United Kingdom Limited
Intellectual Property Law
Hursley Park
Winchester
Hampshire
SO21 2JN
UK

Patents ADP number (if known)

7687858001

Patents ADP number (if known)

If there are more than three inventors, please write their names and addresses on the back of another Patents Form 7/77 and attach it to this form

Patents ADP number (if known)

REMINDER

Have you signed the form?

PROVISION OF POSITION INFORMATION IN CELLULAR
NETWORK DATA TRANSMISSION

5

TECHNICAL FIELD OF THE INVENTION

The present invention relates to the provision of position information in data transmissions within a cellular network .

10

BACKGROUND

15

Increasing numbers of applications using mobile communication devices such as mobile phones or WAP (Wireless Application Protocol) enabled computing devices make use of information about the position of the mobile communication device. For example, emergency services may require the location of a caller to be provided. Commercial applications, too, make use of caller location in order to determine what services or information to offer. These can simply include information about the nearest shop, restaurant or filling station to the caller or may be more complex billing systems for differentially charging the user for a service depending on his whereabouts.

20

25

The most basic information on mobile device position is the location of the cell or sector radio mast (transceiver) which is handling the call, which is usually the nearest to the device. This may be further refined by signal strength information or direction information, if directional antennae are employed. Various alternatives offering more accuracy, like triangulation based on directional signals from several masts or on distance estimates derived from signal strengths or transmission times to several masts have been proposed. Even more accurate position information may be available from the mobile device itself if it is enabled for GPS (Global Positioning System) but this requires additional hardware and software to allow the device to contact the necessary geostationary satellites.

30

35

More detail of the status of wireless location-based services may be found in several articles on the Internet :

40

" Wireless Location System" (Sadhana Kant) at
<http://www.glue.umd.edu/~skant/project621.html>

5 "Location- Based Services offer a Global Opportunity for New Revenue" (Eric
McCabe, Telecommunications Online, October 1999) at
<http://www.telecoms-mag.com/issues/199910/tcs/location.html>

10 "Location-Based Technology pushes the Edge" (R. Boswell,
Telecommunications Online, dated June 2000) at
<http://www.telecoms-mag.com/issues/200006/tcs/location.html>

15 However, the systems described in the above referenced prior art all
presuppose a request for position information, either from the server
hosting the application or from the mobile device itself. This involves at
least two and up to four communication flows before the requesting
application can receive and make use of the position information. It may
also require a private client/server protocol between the device and the
server application.

20 In US patent 5873040, "Wireless 911 Emergency Location, a system is
described for locating the position of an emergency caller by computing a
likely location area from the strength of signal received by several
neighbouring masts. The location area information is applied to a further
database which contains explicit geographic or topographic information
25 based on area and this more detailed information is passed on to the
emergency service to assist with final location of the caller.

30 Mobile communication devices employ various technologies and conform
to various protocols for the transmission and receipt of signals. A common
transmission protocol is the GSM (Global Systems for Mobile Communications)
standard in use in Europe. To allow mobile devices to access the Internet,
which uses HTTP (Hypertext Transfer Protocol) to transmit web pages coded
in HTML (Hypertext Markup Language), the WAP protocol has been developed.
This conforms to basic HTTP and allows WAP enabled devices to receive the
35 core information content of HTML pages in a simplified representation,
excluding pictures, known as WML (Wireless Markup Language). WAP coded
signals may be received and handled directly by Internet Service Providers
whose systems recognise WAP, or may be converted by a gateway computer to
HTTP/HTML form. Internet connection allows mobile device users to access
40 ISP websites and use ISP applications to make retail purchases or obtain
information. Some of these applications, as pointed out above may require

positional information about the communicating mobile device. Such applications request positional information from the mobile device or a network location service after they have been started.

5 Two papers discussing such position information requirements from a conference held in March 2000 are available on the Internet :

"WAP Based Location Services" , S. Souissi and G. Phillips, Motorola, at <http://www.w3.org/Mobile/posdep/MotorolaW3C.html>

10 "Workshop on Position Dependent Information Services", P. King, Phone.Com, at <http://www.w3.org/Mobile/posdep/PDCPositionLoc.html>

15 **DISCLOSURE OF THE INVENTION**

Rather than wait for a service requiring positional information of known accuracy to request it, according to one aspect the present invention provides a method of communicating a request for a service from a mobile telecommunications device to said service via a cellular wireless network including a plurality of transceiver stations, each located in a corresponding cell, comprising the steps of: establishing a wireless connection between said mobile device and one of said transceivers; transmitting a request for the service from the mobile device to the transceiver; determining the position of said mobile device; estimating the accuracy of said position determination; transmitting said request through the network and onward to the service, said transmitted request including position and accuracy information about the mobile device.

30 Such automatic insertion of position information into every transmission obviates the need for specific requests and interchanges for such information. Including an accuracy figure assists the receiving service in being able to determine which services it can provide. For example, mobile cell identification may be enough for weather information but more detail would be required for retail or emergency help information. Whether or not automatic position information is provided in this way may, of course, be a user option so that it could be switched on or off as appropriate.

40 The simplest way of providing position information is just to add the known position of the nearest radio mast (which will normally be the one

allocated by the cellular network to be the primary mast for the call) to the transmitted data signal. This would be rather inaccurate but may be adequate for some applications.

5 Preferably, this would be supplemented by information giving the direction of the mobile device. Such information could be obtained from directional antennae and can be further supplemented by signal strength measurements, giving distance from the antenna. If, however, signals from multiple antennae are used, more accurate position information can be
10 obtained via any of the known methods discussed above, such as triangulation, signal strength or timing of signals received at the multiple antennae.

15 If the mobile device is actually enabled for GPS, it can directly provide its known satellite referenced position in every transmission. The point is not what position sensing technology is used but that position information can be inserted directly and automatically into every transmission from the device.

20 According to a second aspect, the invention also provides a method of communicating a request for a service from a mobile telecommunications device to said service via a cellular wireless network including a plurality of transceiver stations, each located in a corresponding cell, comprising the steps of: establishing a wireless connection between said
25 mobile device and one of said transceivers; transmitting a request for the service from the mobile device to the transceiver; estimating the position of said mobile device from the position of said one transceiver from a table of stored transceiver positions ; and transmitting said request through the network and onward to the service, said transmitted request
30 including said estimated position information about said mobile device.

35 This aspect of the invention has the advantage that position information is provided in a single outbound flow from the mobile device from signals available at a single transceiver.

BRIEF DESCRIPTION OF THE DRAWINGS

40 Figure 1 shows a wireless communications network in which position information is included in data transmissions according to the present invention ;

Figure 2 is a flow diagram illustrating a method of providing position information in a cellular network data transmission according to the present invention;

5 Figure 3 illustrates one way of determining mobile device position used in the method of Figure 2;

Figure 4 illustrates the principle of position accuracy estimation employed in the method of Figure 2; and

10 Figure 5 illustrates an alternative way of determining position in the method of Figure 2.

15 **DETAILED DESCRIPTION OF THE INVENTION**

As shown in Figure 1, a wireless communication network is illustrated in which mobile phones, such as 10 and 11, communicate through a cellular system 12 of radio masts (antennae), such as 14 and 15, base station 17 and network controller 19 with a remote server 20 hosting a position dependent application 21. Communication between the network controller 19 and the server 20 may be wireless , across a link 22 or through the public switched network 24 by landline. The wireless connection of the server may be through the same cellular system 12, though no masts have been shown for added clarity. Within network controller 19 are a location service 26, including an accuracy estimator 27.

20 The mobile phones 10 and 11 are assumed to be internet enabled devices capable of transmitting and receiving packets of information interactively, using the WAP or HTTP protocols, between themselves and the application 21 on server 20 . The application 21 may be any position dependent application providing an information or transaction service. Typical information services may be weather or road condition services or the location of retail, banking or accommodation services. A suitable transaction service could be a chargeable service with differential rates dependent on position such as a telephone charging service or a vehicle access pricing service. The actual application is not important to the invention.

35 40 In the prior art, these services would first be accessed by the mobile device and would subsequently interrogate either the device or the

network as to the position of the user. After the position information is provided, the applications then provide their services in dependence on the result. Some services expect the user to provide its own position before allowing the service to commence so that the user device has to interrogate the network to determine its position before accessing the service proper. This can lead to an excess of information flows back and forth between the mobile device and server which is wasteful.

The invention avoids this by providing as far as possible the position of the calling mobile device in the first outbound transmission to the server when initially requesting the service. To assist the server application in determining what service it can provide, not only the position but also an accuracy figure for that position is provided. The application can limit its response to what is available for a given accuracy of position or it can respond by further interrogation of the mobile device or user.

The operation of the system of Figure 1 will now be described in connection with the flow diagram of Figure 2 and the illustrations of Figures 3, 4 and 5.

In Figure 2, the first step 50 is for one of the mobile devices 10 or 11, which are assumed to be internet enabled, to call up and logon to an Internet Service Provider. At step 51, the mobile user requests a particular service by selection from choices offered by the Internet Service Provider. It is assumed that the mobile device user may choose whether or not to permit its position to be determined and transmitted automatically and that this information is stored in the mobile device. This may be under user control, for reasons of privacy, or may be selectively determined in dependence on the nature of the service request, so that unnecessary position information is not added. In step 52, if position transmission is not authorised, the request is simply transmitted, in step 70, to initiate the service in step 71. If the initiated service requires position information, it must then request it from the user in conventional fashion.

If, however, the mobile device is set up to enable automatic transmission of its position, then in step 53, location service 26 determines whether position data is already in the request. In the case of device 10, which is GPS enabled, the data is already present and can be transmitted directly to the service in step 70.

If position data is not present, as in the case of the device 11, then the location service determines it in step 54 with an appropriate accuracy estimation in step 55. In this embodiment of the invention, the location service simply takes the position it can deduce from receipt of the signal from the device 11 at mast 15. Mast 15 is assumed to be the nearest or one of the nearest masts to device 11, which has been allocated control of the call from device 11 by the cellular network. The basic component of position information is the geographic location of the mast which may be stored in a database. However, further information about the distance of the device from the mast may be obtained from the signal strength and, if the mast has one or more directional antennae, information on a directional range for the device can be obtained. In this case, as schematically illustrated in Figure 3, the position of the device 11 can be determined to be in a sector 30 and within a range delimited by circle 31, as shown by the shaded area 32.

To determine the accuracy of this position estimate, accuracy estimator 27 (ref Figure 4) computes a notional square 40 around area 32 which just contains the extremities of the area. Alternatively, any other regular polygon or a circle may be fitted to area 32.

The estimated or most likely position of device 11 is taken to be the centre of the square, at position P, and the accuracy is estimated to be the half dimension of the square. Clearly, other ways of estimating the position and accuracy from a shaped area are possible, such as determining the centre of gravity of the shape and the mean distance from the centre of gravity to the boundaries.

This determination of position can be adequate for the provision of many services and, returning to Figure 2, the next step is for the location service 26 to open the request packets, in step 56. The location service then adds the position and accuracy information to the HTTP flow from the device 11, in step 57. This is then transmitted in step 70 to initiate the requested service in step 71. The position and accuracy information may be added as a new header portion or may be inserted in a pre formatted header space, initially filled with null values.

The format of the position information is

Mobile_Position: Latitude, Longitude (Latitude Accuracy, Longitude Accuracy)

An example of this would be :

73:23:34N,001:25:54E(000:01:30,000:02:00)

5 This would mean that the device's estimated position was 73 degrees, 23 minutes and 34 seconds North, 1 degree, 25 minutes and 54 seconds East. The accuracy on longitude is 1 minute 30 seconds of arc and on latitude is 2 minutes of arc.

10 In a variant on the above embodiment, if a more accurate position is likely to be required than can be obtained from information on the signal at a single mast, a more complex position calculation can be made by the location service 26, based on the signals received at several masts. One suitable technique is that described in the referenced US patent 5873040
15 which is illustrated in Figure 5. Signals from device 11 are assumed to be received by masts, such as masts 14 and 15 in Figure 1, in each of a cluster of cells, C1, C2, C3, C4. Based on signal strength at each of the masts, a series of likely range circles R1, R2, R3 and R4 may be drawn .
20 The position of the device is most likely to be in the shaded area formed by the intersection of the four circles. This is a much smaller area than can be deduced from signals at a single mast alone and the corresponding accuracy of position is much greater.

25 If encryption of user data is employed, such as by using the SSL (Secure Sockets Layer) protocol, then it is optional whether the added position and accuracy information should also be encrypted. Preferably, the position and accuracy data should flow in clear but, if it is encrypted, this must be with the same key which the serving application uses.

CLAIMS

1. A method of communicating a request for a service from a mobile
5 telecommunications device to said service via a cellular wireless network
including a plurality of transceiver stations, each located in a
corresponding cell, comprising the steps of:

10 establishing a wireless connection between said mobile device and one
of said transceivers;

transmitting a request for the service from the mobile device to the
transceiver;

15 determining the position of said mobile device;

estimating the accuracy of said position determination;

20 transmitting said request through the network and onward to the
service, said transmitted request including position and accuracy
information about the mobile device.

2. A method as claimed in claim 1 in which said position determining
step includes the step of obtaining the position of said one transceiver
25 from a table of stored transceiver positions and the accuracy is estimated
from known cell dimensions.

3. A method as claimed in claim 2 in which said position determining
step includes a further determination based on signal strength at said one
30 transceiver.

4. A method as claimed in claim 1 or claim 2 in which said position is
partly determined by detecting signal direction at said one transceiver.

35 5. A method as claimed in claim 1 in which the position of said mobile
device is determined by analysing signals received at several of the
transceivers.

40 6. A method as claimed in claim 1 in which position is determined by
said mobile device from satellite position reference signals.

7. A method as claimed in any preceding claim in which said position determination is responsive to a request for service.

5 8. A method as claimed in claim 1 in which said position determining step takes place in said network when said device connection is established, said method including the further step of downloading and storing said position and accuracy information in said mobile device for subsequent transmission in the course of a request for service.

10 9. A method as claimed in claim 8 in which said position determining step takes place at intervals subsequently to said device connection being established.

15 10. A method as claimed in any one of claims 1 to 5 in which the device position is determined to lie within a shaped area and accuracy is estimated from the boundaries of a circle or regular polygon fitted to said shaped area.

20 11. A method as claimed in any preceding claim in which said service is an internet based service, said request being transmitted according to a predetermined protocol, said position and accuracy information being placed in a header field of said protocol.

25 12. A method as claimed in claim 11 wherein the protocol is Hypertext Transfer Protocol (HTTP).

30 13. A method as claimed in either claim 11 or claim 12 in which said protocol includes user data, including the steps of encrypting said user data but not said position and accuracy information.

14. A method as claimed in any preceding claim including the step of selectively controlling said position determination and transmission steps.

35 15. A method as claimed in claim 14 in which said selective control step is dependent on the nature of said request.

40 16. A method of communicating a request for a service from a mobile telecommunications device to said service via a cellular wireless network including a plurality of transceiver stations, each located in a corresponding cell, comprising the steps of:

establishing a wireless connection between said mobile device and one of said transceivers;

transmitting a request for the service from the mobile device to the transceiver;

estimating the position of said mobile device from the position of said one transceiver from a table of stored transceiver positions; and

transmitting said request through the network and onward to the service, said transmitted request including said estimated position information about said mobile device.

17. A method as claimed in claim 16 in which said position determining step includes a further estimation based on signal strength at said one transceiver.

18. A method as claimed in claim 16 or claim 17 in which said position is partly estimated by detecting signal direction at said one transceiver.

19. A method as claimed in claim 18 which includes the further step of testing whether position information is already included in said request and making said estimating step conditional on whether positional information is already included or not.

20. A method as claimed in any one of claims 16 to 19 including the further steps of estimating the accuracy of said estimated position information and transmitting said accuracy estimate along with said request.

21. A computer program comprising instructions which, when executed on a computer in a cellular telecommunications system, automatically provides information on the position of a mobile telecommunications device according to a method as claimed in any one of claims 1 to 15.

22. A computer program comprising instructions which, when executed on a computer in a cellular telecommunications system automatically provides information on the position of a mobile telecommunications device according to a method as claimed in any one of claims 16 to 21.

23. A cellular telecommunications system comprising a plurality of transceiver stations forming a network for the transmission of signals from or to any of a plurality of mobile communication devices to an internet based server;

5 a location service means, responsive to a request from a mobile communications device for a service located on such a server, to determine the position of said mobile device;

10 means for estimating the accuracy of said position determination;

means for adding said position and accuracy information to said request for transmission to said server .

15 24. A cellular telecommunications system comprising a plurality of transceiver stations forming a network for transmission of signals from or to any of a plurality of mobile communication devices to an internet based server;

20 location service means, responsive to a request from a mobile communications device for a service located on such a server, to estimate the position of a mobile device, said position estimate being based on the position of the one of said transceiver stations receiving the strongest signal from said device, from a table of stored transceiver positions; and





25 means for adding said position estimate to said request for transmission to said server.

ABSTRACT


PROVISION OF POSITION INFORMATION IN CELLULAR
NETWORK DATA TRANSMISSION

5 A cellular telecommunications system comprises a plurality of
transceiver stations forming a network for transmission of signals between
a mobile communications device and an internet based server hosting an
10 application which is dependent on the position of the mobile device. The
position of the mobile device is provided to the application as part of the
initial request for the service from the device, thus avoiding the need for
multiple flows of information. The position may be based simply on the
known location of the transceiver station with which the device establishes
15 wireless connection, with directional or signal strength range information
added, if available. Alternatively, the position may be estimated more
accurately from the signal received at multiple transceiver stations. In
either case an accuracy estimate can be added to the determined position.

This Page Blank (uspto)

FIG. 1FIG. 4FIG. 3FIG. 5

This Page Blank (uspto)

FIG. 2

This Page Blank (uspto)